REPLY TO PRE-BID QUERIES FOR THE WORK OF PROVIDING & LAYING OF 2000MM, 2200MM AND 2400MM DIA RCC NP-3 PIPELINE FROM MYLASANDRA STP TO DODDABELE STP

Tender BWSSB/CE(WWM-W)/ACE(WWM-N-W)/DCE(WWM-E&W)/TA-2/ 920/2023-24DATED:20.02.2024 BWSSB/2023-24 /WS/Work_INDENT384

Sl. No	Document Name	Page No/Section Name	Statement	Query	Submitted on	Reply
1.	Appendix Price Escalation	On Page 54 v Adjustment for Bitumen	Adjustment for Bitumen	There is no item in BOQ related with Road Restoration Please clarify and incorporate this item weightage in other component	24-02-2024 13:09:30	Refer Addendum.
2.	BOQ	Item No a 13 Sl No 27	For manufacture of RCC NP3 class Pipes by using OPC	On Page 59 for manufacture of RCC NP3 Pipes it is mentioned to use SRC and marked with ISI Please clarify	24-02-2024 13:06:07	Tender condition prevails.
3.	Engineers Requirement Site Office	Clause 27 on Page 45	Requirement of Site Office including furniture survey instruments personal computer Lap Top with accessories and Printers	The same has not been considered in BOQ The cost of the same to be considered during the tender evaluation or delete from the contract	24-02-2024 13:13:29	Tender condition prevails.
4.	Engineers Requirement Transport	On Page 48 Clause No27 5	Requirement of Transport Vehicle One New Top end 6 Plus 1 seated Toyota Innova Crysta ZX fully loaded	For providing vehicle we would like to inform you that recently in Arkavathi Wss Tender the same was included by incorporating to provide vehicle and the capital cost of vehicle will be reimbursed at actual cost under provisional sum excluding insurance The same has not been considered Either you consider the same or delete from the contract	24-02-2024 13:19:23	Tender condition prevails.

5.	Hard Rock in Special Conditions of Contract	Clause 12 on Page 44	The Hard Rock obtained during the execution will not be auctioned by Board Because of restriction in stock of HR in site and safety issues However Rs70 per CuM Plus applicable GST of HR will be recovered from the firm in Running Bill	Please clarify	24-02-2024 13:24:29	Tender condition prevails.
6.	Hard Rock Measurement and payment for Excavation	Sl No 12 3 on Page 65	In case of HR requiring chipping or chiseling measurements shall be taken prior to and after chiseling the volume of rock excavation shall be measured based on this difference Excavation in Rock shall be paid on stack measurement with a deduction of 40 percent in volume for voids However the payment for rock excavation by blasting shall be limited so as not to exceed the volume computed based on trench dimensions as per specifications	Please clarify	24-02-2024 13:33:05	Trench measurements will be considered.

Chief Engineer(WWM-W)
BWSSB